



\* As an option, the Contractor may set the anchor studs after placing concrete barrier using  $\frac{7}{8}$ " dia. cored holes and an approved epoxy grout. Nuts and washers shall be omitted from the embedded ends of anchor studs. No additional compensation will be allowed for this option.

### TYPICAL SECTION

Scale:  $\frac{3}{4}$ " = 1'-0"

Note:  
Straight back parapet shown, see Typical Section for exact configuration.

Note:  
For Sections A-A and B-B see Sheet 2 of 2 of this standard.

APPROVAL	
<i>L.S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 6/3/76	
REVISIONS	
SHA	FHWA
1-11-88	6-8-90
3-13-01	.
7-26-01	.
9-2-03	.

FHWA APPROVAL  
DATE: 10-3-80

STATE OF MARYLAND  
DEPARTMENT OF TRANSPORTATION  
STATE HIGHWAY ADMINISTRATION  
OFFICE OF BRIDGE DEVELOPMENT

ANTI-CLIMB SHIELD FOR  
CHAIN LINK SAFETY FENCES TYPES I AND II

STANDARD NO. BR-SS(3.05)-75-25

SHEET 1 OF 2

SUPER-FENCING NEW STRUCT.