



Note:

1. * Omit concrete haunch by dropping bottom of concrete slab to bottom of top flange on spans of 30'-0" or less c/c of bearings.

APPROVAL	
<i>E. S. Friedman</i> DIRECTOR OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/15/79	
REVISIONS	
SHA	FHWA
3-3-93	.
.	.
FHWA APPROVAL	.
DATE: 12-12-79	.

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

CONCRETE HAUNCH DETAIL FOR
BRIDGE DECKS FORMED WITH TIMBER

STANDARD NO. BR-SS(6.17)-79-98

SHEET 1 OF 1