



Notes:

I.Place vertical paraffin joint, shown hatched, at centerline of pier on

multi-span continous bridges.

2. The placement of adjacent sections shall have a 40 hour delay between placements.

3. Railing and fencing not shown.

\*In order to insure a smooth and acceptable surface, 420.03.II (Construction Joints) will be strictly adhered to.

APPROVAL	
OFFICE OF BRIDGE DEVEL.	
DATE: 6/1/05	
REVISIONS	
SHA	FHWA

STATE OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION OFFICE OF BRIDGE DEVELOPMENT

PARAPET CONTROL JOINT AND DUAL CONDUIT PLACEMENT WITH 42" F-SHAPE PARAPET

FHWA APPROVAL **STANDARD NO.** BR-SS(6.37)-05-247B DATE:

SHEET 3 OF 3

SUPER-CONCRETE