



Notes:

1. The cost of curb including reinforcing, 4" dia. PVC and AASHTO I53 Type I joint seal will be included in Superstructure Concrete item.
2. The cost of anchor bolts and plates will be included in the Railing item.
3. All reinforcing steel shall be epoxy coated.
4. Longitudinal reinforcing steel in the precast slab panel not shown.
5. Prestressing strands in the precast slab panel not shown.
6. For size and spacing of precast slab panel stirrups see precast slab panel details.

* May vary with application.

(USE WITH STD. NO. BR-SS(5.07)-07-375)

APPROVAL	
<i>L. Schuman</i> DIRECTOR	OFFICE OF BRIDGE DESIGN
DATE: 2/8/07	
REVISIONS	
SHA	FHWA
8-3-07	
7-21-08	
FHWA APPROVAL	
DATE:	

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF STRUCTURES

PRECAST CONCRETE SLAB PANEL
CURB DETAIL

STANDARD NO. BR-SS(6.60)-07-377

SHEET 1 OF 1

SUPER CONCRETE WORK