



Note:

1. Splash blocks shall be placed at all scuppers that do not directly outlet onto slope protection or into water and are less than 40' above finished ground.
2. Concrete shall be Mix. No. 1 or better.
3. Cost of splash block(s) complete in place, regardless of alternate (including Selected Backfill) shall be measured and paid for at Contract unit price bid on Slope Protection item. If there is no slope protection in the project then cost to be included in Contract price bid on Scuppers or whichever item(s) scuppers are included in.
4. Alternate Section A-A is to be utilized when riprap slope protection is specified for slopes of bridge. All material for riprap for splash block shall conform to the same requirements for the other riprap slope protection for bridge.

APPROVAL	
<i>L. S. Friedman</i>	DIRECTOR
OFFICE OF BRIDGE DEVELOPMENT	
DATE: 11/14/80	
REVISIONS	
SHA	FHWA
7-28-82	8-24-82
5-6-83	11-29-85
2-14-94	
1-22-01	

FHWA APPROVAL
DATE: 8-20-81

STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF BRIDGE DEVELOPMENT

SPLASH BLOCKS FOR
SCUPPER OUTLETS

STANDARD NO. M(6.04)-80-119

SHEET 1 OF 1

MISCELLANEOUS